

# SLAB-ON-GRADE, BUILT TO LOCK-UP BY INTEGRITY

The Carriage House XL serves a dual purpose - it provides space for a 30'x55' garage or workshop plus over 1400 sq ft of functional space above. The second floor has space for 3 bedrooms, 2 bathrooms, great room, kitchen and dining area, laundry plus storage and is a smart way to add more living space to your property.

Built with our Perma-Column® Foundation, this slab-on-grade house is professionally designed and engineered. Integrity crews will build your home to the lock-up stage which includes exterior walls, roof, windows, doors and metal siding, plus options such as open or closed lean-to's and raised deck. The interior is ready for you and your contractor to take over and complete.

The Carriage House XL also comes with a complete drawing package, including the floor plan for permit application.

### **FEATURES**

- 30'x55' garage or workshop
- Over 1400 sq ft of functional space on the second floor
- Space for 3 bedrooms, 2 bathrooms, great room, kitchen & dining area, laundry and storage
- Options to add open or closed lean-to's and raised deck
- Permit ready engineered and stamped drawings
- Warranty covering labour and materials
- Efficient build schedule of 4 6 weeks\*
- Flexibilty complete the interior your way

\*schedule may vary

#### YOUR HOME. WHEN AND WHERE YOU WANT.












866-974-7678 | sales@integritybuilt.com | integritybuilt.com



## MAIN FLOOR 30'x55'




\_\_\_\_\_ 55' \_\_\_\_\_

866-974-7678 | sales@integritybuilt.com | www.integritybuilt.com



## **SECOND FLOOR 1450 sq ft**



866-974-7678 | sales@integritybuilt.com | www.integritybuilt.com



### **BASE SPECIFICATIONS**

#### DESIGN AND ENGINEERING

- Engineered, stamped drawings
- Complete floor plan layouts

#### FOUNDATION

- 5' Perma-Column® with 4 ply 2x8 laminated posts
- Frost Shield Insulation System

#### WINDOWS AND DOORS

- White, Vinyl, Dual Glaze, Low E Casement windows
- 36" steel door slabs
  - 1/2 Glass at front entry
  - Full Glass at dining room
  - 16' x 8' Overhead doors, white, no operator (if applicable).

\*As per standard plan designs shown

#### EXTERIOR WALLS

- 4 ply 2x8 Laminated posts
- 2x4 horizontal strapping (exterior of post)
- House wrap
- 29 Gauge coloured Metal

#### ROOF

- Engineered roof trusses
- 2x6 strapping
- 7/16" OSB sheathing
- 29 gauge coloured Metal with synthetic underlay

#### WARRANTY

Coverage on labour and materials as follows;

- 1 year: Overhead doors and windows
- 5 years: Defects on supplied material and labour
- 40 years: Metal Finish
- Lifetime: Perma-Column® Foundation

### **AVAILABLE UPGRADES**

- 7/16" OSB Wall Sheathing
- Board and Batten or Horizontal Plank wall metal profiles
- Wainscot metal accent
- Triple Glaze Windows
- Black Windows





POST STRUCTURES

### YOUR HOME. WHEN AND WHERE YOU WANT.

866-974-7678 | sales@integritybuilt.com | www.integritybuilt.com