

# SLAB-ON-GRADE, BUILT TO LOCK-UP BY INTEGRITY

The Shouse makes outstanding use of its space, including a 48'x70' shop that features 3 overhead doors to easily fit your vehicles, toys and tools. The attached residence is 2 floors offering 2660 sq ft of functional space with room for 4 bedrooms, 2 and a half bathrooms, lower kitchen and dining area, great room, upper floor bonus room, laundry and storage.

Built with our Perma-Column® Foundation, this slab-on-grade house is professionally designed and engineered. Integrity crews will build your home to the lock-up stage which includes exterior walls, roof, windows, doors and metal siding, plus options such as a wrap-around lean-to and timber accents. The interior is prepared and ready for you and your contractor to take over and complete.

The Shouse comes with a complete drawing package, including the floor plan for permit application.

### **FEATURES**

- 48'x70' garage and workshop
- 2660 sq ft of living space over 2 floors
- Space for 4 bedrooms, 2 and a half bathrooms, kitchen and dining area, great room, upper floor bonus room, laundry and storage
- Options to add wrap-around lean-to and timber accents
- Permit ready engineered and stamped drawings
- Warranty covering labour and materials
- Efficient build schedule of 4 6 weeks\*
- Flexibilty complete the interior your way

\*schedule may vary

#### YOUR HOME. WHEN AND WHERE YOU WANT.




















# MAIN FLOOR 1330 sq ft





# **SECOND FLOOR 1330 SQ FT**





### **BASE SPECIFICATIONS**

#### DESIGN AND ENGINEERING

- Engineered, stamped drawings
- Complete floor plan layouts

#### FOUNDATION

- Perma-Column® with 2x8 laminated posts
- Frost Shield Insulation System

#### WINDOWS AND DOORS

- White, Vinyl, Dual Glaze, Low E Casement windows
- 36" steel door slabs
  - 1/2 Glass at front entry
  - Full Glass at dining room
  - 16' x 8' Overhead doors, white, no operator (if applicable).

\*As per standard plan designs shown

#### EXTERIOR WALLS

- 2x8 Laminated posts
- 2x4 horizontal strapping (exterior of post)
- House wrap
- 29 Gauge coloured Metal

#### ROOF

- Engineered roof trusses
- 2x6 strapping
- 7/16" OSB sheathing
- 29 gauge coloured Metal with synthetic underlay

#### WARRANTY

Coverage on labour and materials as follows;

- 1 year: Overhead doors and windows
- 5 years: Defects on supplied material and labour
- 40 years: Metal Finish
- Lifetime: Perma-Column® Foundation

## **AVAILABLE UPGRADES**

- 7/16" OSB Wall Sheathing
- Board and Batten or Horizontal Plank wall metal profiles
- Wainscot metal accent
- Triple Glaze Windows
- Black Windows







### YOUR HOME. WHEN AND WHERE YOU WANT.